BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/06/2013-14, Date:05.11.2013 **ITEM NO: 10**

SCHEDULE-B

NAME OF WORK: Providing BS Slab drain and metalling in Kerekodi road, near Nisarga Layout at Abbegere in Ward No.12. in Shettyhalli Sub Division .

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **RAVIKUMAR B T .**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications.	Cum	176.4	143.21	Rupees One Hundred Forty Three and Twenty One Paise Only
2	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 cms thick complete as per specifications.	Cum	1080	324.14	Rupees Three Hundred Twenty Four and Fourteen Paise Only
3	Earthwork in surface excavation in Hard soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications.	Cum	1092.7	167.17	Rupees One Hundred Sixty Seven and Seventeen Paise Only
4	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specifications including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding Materials to fill up the interstices of coarse aggregates, watering and compacting to the required density Complete as per Specification.	Cum	468.3	1405.62	Rupees One Thousand Four Hundred Five and Sixty Two Paise Only
5	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specifications including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding Materials to fill up the interstices of coarse aggregates, watering and compacting to the required density Complete as per Specification.	Cum	234.15	1527.94	Rupees One Thousand Five Hundred Twenty Seven and Ninety Four Paise Only
6	Carriage of mixed materials 10 Kms, For items of Sl.no 1.c) rs. 5.20 per cum/km. complete as per specifications.	Cum	702.45	53.0	Rupees Fifty Three Only
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading complete as per specifications.	Cum	1269.1	68.62	Rupees Sixty Eight and Sixty Two Paise Only

B. T. Ravikumar

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,